

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Drilling of Borewells and Providing Pipelines at Vidyaranyapura area in ward no 09 (Vidyaranyapura)

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging technical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each	3768	Rupees Three Thousand Seven Hundred Sixty Eight Only
2	100	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.), with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	347	Rupees Three Hundred Forty Seven Only
3	100	50 to 100 m	Rmtr	442	Rupees Four Hundred Forty Two Only
4	100	100 to 150 m	Rmtr	456	Rupees Four Hundred Fifty Six Only
5	100	150 to 200 m	Rmtr	536	Rupees Five Hundred Thirty Six Only
6	100	200 to 250 m	Rmtr	634	Rupees Six Hundred Thirty Four Only
7	100	250 to 300 m	Rmtr	700	Rupees Seven Hundred Only
8	100	300 to 350 m	Rmtr	825	Rupees Eight Hundred Twenty Five Only
9	100	350 to 400 m	Rmtr	900	Rupees Nine Hundred Only
10	140	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1325	Rupees One Thousand Three Hundred Twenty Five Only
11	36	Providing 250mm dia PVC Pipe 6kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1100	Rupees One Thousand One Hundred Only
12	2	Providing and fixing Borewell Cap & Clamp Set etc., complete and as per the directions of the Engineer-in-charge of the work	Set	1800	Rupees One Thousand Eight Hundred Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
13	2	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required accessories such as suction, casing suction strainers sand guard Non return valve etc. complete. The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps etc., complete and as per the directions of the Engineer-in-charge of the work	No	63498	Rupees Sixty Three Thousand Four Hundred Ninety Eight Only
14	640	GI Pipe 50 mm'B' class etc., complete and as per the directions of the Engineer-in-charge of the work	M	415	Rupees Four Hundred Fifteen Only
15	108	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	180	Rupees One Hundred Eighty Only
16	2	Providing non-return valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	No	1800	Rupees One Thousand Eight Hundred Only
17	36	Providing Gate Valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	No	1800	Rupees One Thousand Eight Hundred Only
18	2	Supplying and Fixing Out Door Panel up to 15 HP etc., complete and as per the directions of the Engineer-in-charge of the work	No	15500	Rupees Fifteen Thousand Five Hundred Only
19	1320	Submersible Cable 1x3x6.0 Sq.mm etc., complete and as per the directions of the Engineer-in-charge of the work	M	144	Rupees One Hundred Forty Four Only
20	108	Labour charges for erection as new /repaired submercible pumpset along with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset should be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	L	88	Rupees Eighty Eight Only
21	2	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	292	Rupees Two Hundred Ninety Two Only
22	70	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A 4 core 16 Sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	150	Rupees One Hundred Fifty Only
23	70	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	11.88	Rupees Eleven and Eighty Eight Paise Only
24	60	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	76	Rupees Seventy Six Only
25	8	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	335	Rupees Three Hundred Thirty Five Only
26	2	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No	270	Rupees Two Hundred Seventy Only
27	2	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	2999.7	Rupees Two Thousand Nine Hundred Ninety Nine and Seventy Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
28	12	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No	174	Rupees One Hundred Seventy Four Only
29	2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN etc., complete and as per the directions of the Engineer-in-charge of the work	No	1715	Rupees One Thousand Seven Hundred Fifteen Only
30	46800	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete and as per the directions of the Engineer-in-charge of the work	Sq Cm	0.35	and Thirty Five Paise Only
31	38.4	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications.	Cum	952.94	Rupees Nine Hundred Fifty Two and Ninety Four Paise Only
32	76.8	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shirry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strata by Manual Means etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	262	Rupees Two Hundred Sixty Two Only
33	340	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and including lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the excecavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	207	Rupees Two Hundred Seven Only
34	48	Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications.	Cum	3221.34	Rupees Three Thousand Two Hundred Twenty One and Thirty Four Paise Only
35	28.8	Refilling the basement and pipeline treanches with seclcted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	103	Rupees One Hundred Three Only

"NO OF CORRECTION NIL"

"NOT APPROVED"

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))